BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

Name of Work: Constructions of Anganavadi Building at Karekallu Village (Vinayakanagara) Bagalagunte in Ward No.14.

Sl. No	Description of work	Unit	Qty	Sanctioned Approved Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Supplying water storage tanks made of virgin polymer (LLDPE) with two layers outer black or blue and inner white layer of approved quality and make, conforming to I.S.I./ISO/SSI Complete as per specifications.	L	1000.00	6.10	Rupees Six and Ten Paise Only
2	Providing and fixing on wall surface 4.0kg/sq.cm H.D.P.E rain down water pipes 110mm outer dia approved make and brand with necessary specials like shoes bends and offsets fixed with iron clamps, walls plugs, screws, including cost of materials, labour, Complete as per specifications.	Mtr	48.00	466.40	Rupees Four Hundred Sixty Six and Forty Paise Only
3	Providing and fixing white vitreous china clay, water closets Orissa pattern of size 580 x 440mm with integral type footrests, 100m S or P trap, (approved make) cutting and making good the wall and floor wherever required, including cost of materials, labour Complete as per specifications.	Pan	2.00	1569.86	Rupees One Thousand Five Hundred Sixty Nine and Eighty Six Paise Only
4	Providing and fixing in position brass bib cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads Complete as per specifications.	Each	2.00	147.34	Rupees One Hundred Forty Seven and Thirty Four Paise Only
5	Providing and fixing white vitreous china clay, surgeon type wash basin of size 660x460mm with single 15mm C.P brass pillar taps with single elbow operated levelers, C.I. /M.S. brackets, 32mm C.P. brass waste of standard pattern, painting of fitting and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour Complete as per specifications.	Unit	1.00	3142.90	Rupees Three Thousand One Hundred Forty Two and Ninety Paise Only
6	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fitting including fixing the pipe clamp at 10.00 meter spacing. This includes jointing of pipe and fittings with one step CPVC solvent cement and testing of joints Complete as per specifications.	M	38.00	127.20	Rupees One Hundred Twenty Seven and Twenty Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer,
Dasarahalli Division,